



CENER
ADItech

CENTRO NACIONAL DE
ENERGÍAS RENOVABLES
NATIONAL RENEWABLE
ENERGY CENTRE

PHOTOVOLTAIC SOLAR ENERGY DEPARTMENT

QUALITY ASSURANCE OF PV MODULES AT ORIGIN AND DESTINATION

CENER OFFERS A SERVICE ORIENTED TO NEW PV INSTALLATIONS WITH THE FINAL GOAL OF GUARANTEEING THE QUALITY DURING ALL THE STAGES INVOLVED ALONG THE CONSTRUCTION OF THE FINAL PV PLANT

CENER'S PROCEDURE OR ADAPTATION OF TECHNICAL ADVISOR'S PROTOCOL



Monitoring at factory

- Quality & productive system
- In-line & out-line test
- Test in accredited lab.
- Supervision pre-shipment

Warranty after transport

- Verification absence of damages after transport
- Characterization by EL
- Measurement just at the arrival of the PV modules

Warranty after installation


- Verification absence of damages after mounting
- Characterization by EL
- Use of special system (CELSOS) for measurements

SUPERVISION AND CONTROL OF MODULES AT ORIGIN

- Previous auditory of quality and productive systems of the factory (according to standard IEC/TS62941)
- Monitoring during manufacturing of hired PV modules
 - According to contract supplied-customer or by CENER's
 - Technical revision of materials, equipment, processes, documentation, etc.
 - Lot definition: sampling according to ISO2859-1
 - Delivery contract deadlines will not be altered
- "In-line" test: inserted in the manufacturing process
 - Applicable to the complete production (i.e.: Pmax, EL)
- "Off-line" test: outside the manufacturing process
 - Applicable to representative samples for MQS requirements
 - Some test can be carried out in-situ by technical personnel supervised by CENER experts
 - Other test (i.e.: LID, diodes, etc) must be imperative performed in accredited laboratory, such as CENER
- CENER has designed a specific protocol to ensure the quality of the manufactured PV modules
 - Adaptable to the specific project or client requirements
- Supervision shipment: documentation & packing revision



PV module during its manufacturing process



Peel test



LID test (performed inside)



Ciudad de la Innovación, 7
31621 Sarriguren (Navarra) · Spain
T + 34 948 25 28 00
info@cener.com / www.cener.com

WARRANTY AFTER MODULE´S TRANSPORT

- Verification of absence of potential damages during the transport of the modules to the PV plant
- Characterization of the modules just after their arrival to the PV plant
- Measurement of a representative sample for each lot/shipment
 - Application of standard ISO2859-1 to determine the size of the sampling
- Capture of high quality electroluminescence (EL) images
- Use of a special mobile laboratory to perform the EL measurements
- Modality of measurements adapted to the client´ s needs:
 - a) Measurements carried out by CENER´ s technicians displaced to the PV plant
 - b) Training client´ s personnel, lab assembly, equipment release and on-site supervision during first measurements
- Analysis of results performed always by CENER´ s expert technicians



Mobile laboratory to capture EL images of modules at their arrival at the PV plant




CENER´ s technician performing EL measurements inside the mobile laboratory

WARRANTY AFTER THE MODULE´ S ASSEMBLY


- Verification of absence of damages during the final assembly
- Characterization of the modules already installed and connected
- Capture of high quality electroluminescence (EL) images
- Use of CELSOS system developed by CENER for measurements
 - Possibility of measuring during the entire day/night (24/7)
 - Suitable for measurements of PV plants up to 1500V of Vsys
 - Electrical biasing of the PV modules at array or inverter level
 - Advanced processing of EL images (sharpness improvement, borders detection, perspective correction, automatic detection of main defects, etc)
- Direct comparison with EL image captured at module´ s arrival



CENER technician taking EL measurements on the field



Set-up schematic of CELSOS system



(Left) EL image of 4 PV modules captured on the field; (Right) Individual EL images after processing

